

ANANDA CHANDRA COLLEGE
(GOVERNMENT SPONSORED)
AFFILIATED TO: UNIVERSITY OF NORTH BENGAL

Office of the Principal
P.O. & Dist. JALPAIGURI, WESTBENGAL,
INDIA, PIN CODE - 735101



E-mail: accjal@gmail.com
Website: www.accollege.in

Ref. No. 2023-24/QT/555

Date: 29.2.2024

Sub: Notice Inviting Quotation

All Authorized Contractors, are hereby requested to apply for the Development Work of A.C. College, Jalpaiguri Municipality. All the necessary documents such as Pan Card, Trade License Certificate, G.S.T. Certificate, last year I.T. return certificate (with Self Attested), & payment certificate of last two year for Similar type of works. Earnest Money @ 2.5 % (two point five zero) of the schedule amount is to be enclosed in the form of D C R in favour of the Principal, A.C College is to be enclosed

The name of the work Should clearly be written in the envelop, The Schedule of work is attached herewith.

DATE OF DROPPING QUOTION IN THE QUOTATION BOX:- 07/03/2024 UP TO 01:00 PM

Date of Opening Quotation: 07-03-2024 at 1.30 p.m.

Sl. No	Name of Work	Ward No	Amount	Earnest Money
1.	Repairing Of Boundary Wall At South Side Of A.C Collage Building In Ward no - 21 Under Jalpaiguri Municipality.	21	87475.00	2187

Principal
29/2/24

A.C. College Jalpaiguri

Principal
Ananda Chandra College
Jalpaiguri

Date: 07/03/2024

Memo No: _____ A (7)/M

Copy to-


- 1) Executive Officer, Jalpaiguri Municipality
- 2) Sub- Divisonal Officer
- 3) B.D.O sadar




Schedule Of Work For Repairing Of Boundary Wall At South Side Of A.C Collage Building In Ward no - 21 Under Jalpaiguri Municipality.

Sl No	Description of Item of works	Quantity	Unit	Rate	Amount
1	Dismantling of masonry work except cement concrete or artificial stone, flooring, reinforced cement concrete, stacking the same serviceable materials and removing rubbish as directed.	5.62	Cum	447.00	2512.14
2	125 mm brick work of 1st class bricks with 4:1 cement mortar etc. Complete as per direction.	12.00	Sqm	667.00	8004.00
3	Scrapping off old plaster as per direction.	512.00	sqm	11.00	5632.00
4	Cement - Plaster (in Wall, Floor, ceiling etc.) with sand and cement mortar including rounding off or chambering corium as directed and racking out points etc. Complete as per direction. (1) with 1:6 cement mortar (2) 15mm thick	180.00	sqm	138.65	24957.00
5	Ordinary cement concrete (mix 1:1/2:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement.	0.89	cum	5781	5145.09
6	Priming one coat to steel surface with synthetic or oil bound primer of approved quality including smothering surface by sand paper etc. Complete.	30.00	Sqm	31	930.00
7	Painting With best quality synthetic enamel paint of approved make and brand including smothering surface, by sand paper. Coats other than white.	30.00	Sqm	86	2580.00
8	Color washing with any shade with strainers as per direction Coats yellow.	512.00	Sqm	21.39	10951.68
9	Labor For taking out damaged barbed wire from fencing wall.	4.50	%MTR	129.00	580.50
10	Plaster (to wall, floor, ceiling etc) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including threading, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over concrete surface] (f) With 1:6 cement mortar (c) 15 mm thick plaster Plaster= 190 sqm	450.00	MTR	26.90	12105.00
Total =					73397.41
G.S.T @18% Of Schedule Amount (A)					13211.53
Total =					86608.94
(B) Cess 1% Of Schedule (A+B)					866.09
Grand Total					87475.03
Say Rs					87475.00

(EIGHTY SEVEN THOUSAND FOUR HUNDRED SEVENTY FIVE ONLY)


 Technical Advisor
 JALPAIGURI MUNICIPALITY
 JALPAIGURI


 Principle
 A.C Collage (Sc & Arts)
 Jalpaiguri